Mysql主从配置

主数据库操作

1. 修改主数据库部署文件das.yaml, 共修改4处

```
apiVersion: v1
kind: ConfigMap
metadata:
  namespace: master-slave
  name: dsb-das-mysql-cnf
  labels:
    app: dashboard-additional-services-0.1.0
    release: dsb-das
data:
  mysql.cnf: |-
    [mysqld]
    max_connect_errors=10
    max_connections=500
    max_user_connections=300
    log-output=FILE
   log-error=/var/log/mysqld/mysqld.log
                                                     修改
    general_log=0N
    general_log_file=/var/log/mysqld/mysqld_log.log
    slow_query_log=0N
    slow_query_log_file=/var/log/mysqld/mysqld_slow_query.log
    long_query_time=10
                                                     新增
   server id=1
    log-bin=/var/log/mysqld/mysqld_bin
    max_binlog_size=500M
    expire_logs_days=99
    interactive_timeout=1800
    wait_timeout=1800
    innodb_buffer_pool_size=8G
    sync_binlog=1
    query_cache_size=0
```

```
template:
220
          metadata:
            labels:
              app: dashboard-additional-services-mysql
              app version: 0.1.0
              release: dsb-das
          spec:
            containers:
            - image: 172.31.215.191:5000/iie-mysql:5.6.51
228
              name: dsb-das-mysql-container
              volumeMounts:
              - mountPath: /var/lib/mysql
                name: mvsql-volume
232
              - mountPath: /var/log/mysqld
                name: mysql-bin-volume
              - mountPath: /etc/mysql/conf.d
                name: mysql-cnf-volume
```

```
volumes:
- name: mysql-volume
hostPath:
path: /workspace/.mysql-data
type: Directory
- name: mysql-bin-volume
hostPath:
path: /workspace/.mysql-data
type: Directory

- name: mysql-cnf-volume
configMap:
name: dsb-das-mysql-cnf
```

2. 重启主数据库

```
kubectl delete -f das.yaml
kubectl apply -f das.yaml
```

3. 进入主数据库执行以下命令

```
GRANT REPLICATION SLAVE ON *.* to 'slave'@'%' identified by 'slavedb@4829';
```

- 4. 同步主数据库数据到从数据库
 - 主数据库上锁

```
flush tables with read lock;
```

查询binlog相关信息

```
show master status;
```

- 拷贝主数据库所在服务器的数据库内容 (/workspace/.mysql-data)到从数据库所在服务器的数据库目录 (/workspace/.mysql-data)
 - 不要拷贝auto.cnf文件
 - 不需要拷贝mysqld_bin.*等binlog文件
 - 不需要拷贝mysql.log,mysqld_log.log以及mysqld_slow_query.log文件
- 拷贝完成后去除数据库锁

```
unlock tables;
```

从数据库操作

1. 启动从数据库,注意根据实际环境修改slave.yaml的相关配置,包括数据库镜像ip地址等

```
kubectl apply -f slave.yaml
```

- 2. 连接从数据库执行命令
- master_user和master_password为主数据库设置中第三步对应信息
- master_log_file和master_log_pos为查询binlog获取的相关信息

```
change master to master_host='dsb-das-
mysq1',master_user='slave',master_password='slavedb@4829',master_log_file='mysqld_bin.000001',ma
ster_log_pos=319,master_port=3306;
```

3. 开启同步,并查看slave状态

```
start slave;
show slave status \G;
```

4. 在主数据库插入记录,并在从数据库查询;然后删除主数据库中插入的记录,在从数据库中查询,验证是否同步。